

Lot Detail	
Lot No. :	Ban-61/2025-26
Lot Description :	Construction of Regulator (3-Vent: 1.50m x 1.80m) on Kumuria Khal at Sonali Bazar, Union- Mognama, Upazilla-Pekua, Dist- Cox's Bazar under "Operational Expenditure for Goods and Services (Economical code-3258137)" under Cox's Bazar W D Division-2, BWDB, Bandarban during FY 2025-26.

Bill of Quantities

Table Name : Bill of Quantities									
Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)
1	1	04-180-00 (BWDB)	Site preparation by manually removing all miscellaneous objectional materials from entire site and removing soil up to 15cm depth including uprooting stumps, jungle clearing, leveling dressing etc. complete as per direction of Engineer in charge.	Sqm	18000				
2	1	01.1 (PWD)	Erection and maintenance of semi permanent site office and removal of the same after completion of work in accordance with the conditions of contract. In addition to the office required for own use, the contractor shall provide and maintain furnished site office for the use of Engineer-in-charge and his staff. The site office must have tiles floor, adequate foundation, brick walls, false ceiling of gypsum board and all windows are to be glazed, shuttered and provided with steel grill. Outside and inside wall surface are to be painted on plaster acceptable to the Engineer-in-charge. The site office shall be maintained in a secure condition by the contractor until the completion of the contract and shall be provided with electricity, water supply, wash rooms and sewerage facilities. All doors shall be fitted with approved locks and windows shall be provided with screen/blinds. Before construction the contractor shall submit plans and drawings showing proposed details and location for the site office, including foundations, access roads, shades, layout of electrical and water supply and hard standings there for the approval of Engineer-in-charge. The Engineer-in-charge may require revision of the plans prior to giving approval for construction. The contractor shall also submit detailed proposed furniture, fittings and other items of equipment and plant to the Engineer-in-charge	job	1				

			for approval. These items shall be of the standard quality suitable for site. The office, complete with furnishings, fittings, access roads and hard standings shall be ready for occupation by the Engineer-in-charge within 28 days of the date when the contractor first occupies the site. The contractor shall provide day and night guards and an attendant for the field office. At the end of the contract all materials, equipment and plant, furniture, fittings recovered from dismantling the office and removing access road will be the property of the contractor. No interim payment shall be certified unless engineer's office with required facilities are constructed and accepted by the Engineer-incharge. (This is a time related item; proportionate payment for this item shall be made distributing in each bill on the basis of percentage progress of the whole works under contract) Engineer's site office of minimum 38 sqm plinth area with providing necessary facilities including office furniture, 24000 BTU air cooler, umbrella, crookeries, water purifier, PC with monitor, uninterruptible power supply (UPS), laser jet printer (minimum 20 ppm), LED flood light fittings (Halogen) for sight security etc. 01.1.3: Engineer's site office of minimum 38 sqm plinth area with providing necessary facilities including office furniture, 24000 BTU air cooler, umbrella, crookeries, water purifier, PC with monitor, uninterruptible power supply (UPS), laserjet printer (minimum 20 ppm), LED flood light fittings(Halogen) for sight security etc.						
3	1	40-620-00 (BWDB)	Supplying new Synthetic bags at site : 40-620-20: Capacity 75 kg.	No	24375				
4	1	40-640-00 (BWDB)	Labour charge for filling empty gunny or synthetic bags with sand or earth, sewing the end with sutly, including carring and placing under water position within the site as per direction of Engineer -in-Charge. 40-640-20: Capacity : 75 kg (Fill Volume = 0.040 cum)	No	24375				
5	1	16-450-00 (BWDB)	Earth work by manual labour with clayey soil (minimum 30% clay, 0-40% silt and 0-30% sand) in construction of cross bundh/ ring bundh as per design and specification with all leads and lifts, throwing the earth in layers not exceeding 150mm in thickness, including breaking clods, rough dressing, clearing the iungle. removing	cum	5264.780				

			stumps, dug bailing and 75mm cambering etc. complete as per direction of Engineer in charge.						
6	1	02.1 (PWD)	Earth work in excavation in all kinds of soil for foundation trenches including layout, providing center lines, local bench-mark pillars, levelling, ramming and preparing the base, fixing bamboo spikes and marking layout with chalk powder, providing necessary tools and plants, protecting and maintaining the trench dry etc., stacking, cleaning the excavated earth at a safe distance out of the area enclosed by the layout etc. all complete and accepted by the Engineer-in-charge, subject to submit method statement of carrying out excavation work to the Engineer-in-charge for approval. However, engineer's approval shall not relieve the contractor of his responsibilities and obligations under the contract. 02.1.2: Earthwork in excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead	cum	8749.360				
7	1	02.1 (PWD)	Earth work in excavation in all kinds of soil for foundation trenches including layout, providing center lines, local bench-mark pillars, levelling, ramming and preparing the base, fixing bamboo spikes and marking layout with chalk powder, providing necessary tools and plants, protecting and maintaining the trench dry etc., stacking, cleaning the excavated earth at a safe distance out of the area enclosed by the layout etc. all complete and accepted by the Engineer-in-charge, subject to submit method statement of carrying out excavation work to the Engineer-in-charge for approval. However, engineer's approval shall not relieve the contractor of his responsibilities and obligations under the contract. 02.1.3: Added rate for each additional 0.5 meter depth exceeding 1.5 meter.(7)	cum	19948.870				
8	1	02.1 (PWD)	Earth work in excavation in all kinds of soil for foundation trenches including layout, providing center lines, local bench-mark pillars, levelling, ramming and preparing the base, fixing bamboo spikes and marking layout with chalk powder, providing necessary tools and plants, protecting and maintaining the trench dry etc., stacking, cleaning the excavated earth at a safe distance out of the area enclosed by the layout etc. all complete and accepted by the Engineer-in-charge, subject to	cum	28698.230				

			submit method statement of carrying out excavation work to the Engineer-in-charge for approval. However, engineer's approval shall not relieve the contractor of his responsibilities and obligations under the contract. 02.1.4: Added rate for each additional 0.5 meter depth exceeding 1.5 meter.(18)						
9	1	16-620-00 (BWDB)	Shoring for slope protection of foundation trench, canal, embankment, road, pond etc. as per design slopes, grades including removal of spoils to a safe distance as per direction of Engineer in charge. 16-620-30: By local hard wood ballah post of 6.0m length, 125mm dia, 1.0m c/c, and 2.0m drive with 6.0m long bamboo of average 75mm dia, @ 1.0m c/c and 2.0m drive with drum sheet walling and average 70mm dia half split bamboo batten @ 2.0m c/c fixed with nails.	Sqm	1520.000				
10	1	01.08 (LGED)	Bench Mark Pillar: Manufacturing, supplying & fixing in position RCC (1:2:4) Bench Mark Pillars of size 150mm x 150mm x 750mm, with 400mm x 400mm x 100mm base having 3 nos. 10mm dia MS bar each way at base, 4 nos. 10mm dia vertical bar and 8 nos. 6mm dia tie, including cost of form works, concreting, reinforcement, plastering at top, inscribing on exposed surface, finishing surface, curing, earth cutting, embedding 450mm below GL., backfilling, ramming etc. complete as per direction of E-I-C.	Nos	4				
11	1	09.05 (PWD)	Providing and making point welding at contact point of the spiral binders at reasonable intervals with the main reinforcements by electric arc welding for construction of cast in situ bored pile carefully with highly oxidized electrodes, making the points prominent and accepted by the Engineer-in-charge (Rate is inclusive of all materials labour, tools and plants, electricity and all equipment).	Point	100073.000				
12	1	09.6 (PWD)	Providing and making welded splice over two sides of contact by welding of minimum 300 mm length at the lap of main reinforcement in re-bar cage to be placed in bore-hole where necessary by electric arc welding with highly oxidized electrodes making the joint prominent all complete and accepted by the Engineer-in-charge. (Rate is inclusive of all materials labour, tools and plants, electricity and all equipment).	m of weld	24.000				
13	1	4.07.01	BCIS: Boring for cast-in-situ	m	4243.500				

		(LGED)	piles up to the required depth and specified diameter with driving temporary steel casing (shall be 8mm thick with necessary stiffener bands and sharp edge at bottom and provided up to non-collapsible strata from the existing ground level but not less than 4.0 m) in all types of soils including min. 2-chamber slurry tank, drilling with bentonite circulation (Dry Bentonite powder of liquid limit of minimum 350 shall be mixed with water @ minimum 4% by weight to make the fresh drilling fluid of viscosity between 32-50 seconds and density less than 1.1gm/cc), maintaining fluid level inside casing at all time at least 2 m higher than outside the casings, washing bore hole by air lift cleanup method with fresh bentonite slurry until the slurry from bore hole bottom have density less than 1.15gm/cc and sand content is less than 4%, make the bore hole ready for concreting including disposal/removal of all bored material, hire charge of mechanical winch machine/ skid mounted mechanical table drive rotary/ hydraulic rotary boring equipment, derrick, trimie pipe, cost of fuel, lubricant, mobilization, demobilization, spares, insurance coverage, water, electricity and other charges all complete as per design, drawing, specification and direction of E-I-C. Contractor shall submit the methodology of cast-in-situ pile work including information on boring equipment, sequence of boring & casting, quality control, disposal of spoils, test result of materials to the E-I-C for approval before commencing any boring operation. Boring and excavation for a pile shall not commence until 24 hours after completion of any pile within radius of 6 meters c/c. Cost of collecting, conveying, loading, transportation of spoils/mud accumulated during boring of cast-in-situ pile with all lifts and lead is included in this unit rate. The spoils must be dumped in an unobjectionable place outside the site premises with minimum traffic disruption and the procuring entity will not be responsible for any irregularities by the party regarding dumping of the spoils. Note: Boring method shall be selected as per instruction given in the drawing. 4.07.01.01.04: 700mm diameter						
14	1	4.07.03 (LGED)	RCC-25SCCM: Reinforced cement concrete work for cast-	Cum	1633.750				

			in-situ pile with minimum cement content relates to mix ratio 1:1.5:3 and maximum water cement ratio 0.4 having minimum required average compressive strength, $f'_{cr} = 33.5$ Mpa and satisfying a compressive strength $f'_c = 25$ Mpa at 28 days on standard cylinders as per standard practice of code AASHTO/ ASTM and cement conforming to BDS EN 197-1 : 2003 CEM-II/A-L/M/V/W 42.5N, high range water reducing and retarding admixture of complying type G under ASTM C 494 (Doses of admixture to be fixed by the mix design), sand of minimum FM 2.5 and 20mm down well graded crushed stone chips broken from boulders (Preferably stone chips from Madhyapara, Dinajpur, LAA value not exceeding 30) conforming to ASTM C 33, including breaking chips, screening through proper sieves, placing & maintaining re-bar cage in position, jointing longitudinal bars by welding or re-bar coupling method, placing and removing tripod/ derrick as per requirement, mixing in standard mixture machine with hopper, maintaining allowable slump of 150mm to 200mm, placing a sliding plug or barrier to prevent direct contact between the first charge of concrete in the pipe of the tremie and the water of drilling fluid, pouring the concrete in bore hole with the help of tremie pipe, maintaining the tremie pipe immersed in concrete by at least 1.5m throughout the period of concreting etc. including cost of all materials, labour, equipment and all incidental charges but excluding the cost of reinforcement and its fabrication, welding, coupling and placing etc. all complete as per design, drawing, specifications and direction of the E-I-C. The contractor shall maintain a continuous record of the volume of concrete used and the level of the concrete in the pipe. Any deviations from the theoretical, or expected, volume/ level relationship shall be immediately reported to the E-I-C. Additional quantity of cement to be added if required to attain the specified strength to be provided by the contractor at his own cost. Note: Using Concrete Mixer						
15	1	09.7 (PWD)	Labour for breaking head of hardened cast in situ bored pile/ pre-cast pile up to a required length by any means but without damaging the rest and removing the dismantled	Cum	42.620				

			materials such as concrete to a safe distance including scraps and cleaning concrete from steel/ M.S. rods, straightening and bending of pile bars, preparation and making platform where necessary, carrying, all sorts of handling, stacking the same properly after clearing, leveling and dressing the situ						
16	1	4.07.23 (LGED)	SLT: Conducting static load test as per ASTM D 1143 or equivalent standard for the cast in situ/ pre-cast pile providing required land development (earth exavation, sand filling, sub-base, cement concrete work, bullah palisading etc.), Crib wall (sand bags, brick works, CC blocks etc.) depending on test loading, scaffolding, bracing, jacks, pressure test gauge, loading unloading, arranging other necessary plants and equipment including staging, mobilization, demobilization, cost of empty gunny/ fertilizer/ plastic bag, concrete block/ steel sheet, sand and filling sacs/ empty gunny/fertilizer/plastic bags, switching, loading and unloading, record readings and preparation of results in standard forms and other incidental charges as per standard practice and procedures including submission of load test report, furnishing all graph and chart etc. complete in all respects approved and accepted by the E-I-C. Before commencing load test, Contractor shall submit methodology along with combined calibration report for conducting load test to the E-I-C for approval. The Testing firm will be selected taking prior approval of procuring entity. The methodology of static load test and driving logs/ boring & pouring logs shall be the part of test report. Load Test and Report shall be conducted under the supervision of a professional Geotechnical Engineer registered in the Bangladesh Professional Engineers Registration Board (BPERB), Institute of Engineers Bangladesh (IEB). [Cost of Combined Calibration Test (Hydraulic Jack, pressure gauge & electric/hydraulic pump) has been included in all sub-items.] 4.07.23.02: Above 75 MT and up to 125 MT	each	3.000				
17	1	44-240-00 (BWDB)	Supplying at site U-Type hot rolled steel sheet pile of different section of Phosphorus=0.04%(Maximum), Sulphur = 0.04% (Maximum),	M. ton	40.610				

			Tensile strength= > 490 N/mm ² , Yield strength = >295 N/mm ² , Elongation =17% (Minimum) including all taxes, freights, incidental charges etc. complete as per as per detail technical specification and direction of the Engineer -in-charge. 44-240-10: U-Type, hot-rolled steel sheet pile width= 400mm to 600mm: height= > 100mm, Thickness >=10.5mm. (◆0.50mm)						
18	1	44-290-00 (BWDB)	Driving steel sheet piles of various sections and weights in any type of soil, by mechanical device including handling and placing in position including supply of all materials and equipments related with driving of sheet piles including correcting leaning beyond tolerance and other defects etc. complete (measurement will be taken on projected width x height) as per direction of Engineer in charge. 44-290-30: U-Type or any other type : Upto 6.50 m depth.	Sqm	317.250				
19	1	44-320-00 (BWDB)	Cutting of steel sheet piles to design length and shape as per requirement in design and drawing and as per direction of Engineer in charge. 44-320-20: Above 10mm thick.	m	28.400				
20	1	44-340-00 (BWDB)	Fabrication and construction of corner Joints in steel sheet piles including cutting, welding, shaping as per design and specification and as per requirement including supply of necessary welding materials, equipments and other accessories as per specification and direction of Engineer in charge.	m	24.000				
21	1	76-180-00 (BWDB)	Cleaning corrosion and rust from the surface of steel with power brush etc. Complete including the cost of all materials as per direction of Engineer in charge.	Sqm	2250.360				
22	1	72-180-00 (BWDB)	Provide 1 (one) coat of Zinc phosphate as primary coat and 2 (two) coat of coaltar epoxy coat over primary coat to steel surface with paint of approved colour etc. complete including the cost of all materials as per direction of Engineer in charge.	Sqm	2250.360				
23	1	44-310-00 (BWDB)	Supplying and placing 20mm thick hessian cloth impregnated with bitumen in expansion joints or on top of sheet piles as per specification and direction of Engineer in charge.	Sqm	34.280				
24	1	20-495-00 (E.R) BWDB)	Polythene Sheet : (1.0 kg per 6.50 sqm).	Sqm	536.700				
25	1	12-310-00 (BWDB)	Bailing out of water with all leads and lifts by manual labour or pump, with all arrangements for protection of ring bund and side slopes of foundation pit	Cum	164905.650				

			against erosion or washout etc. complete actual volume of work will be measured by sounding method before starting the work) as per direction of Engineer in charge. 12-310-20: By pump.						
26	1	4.06.03 (LGED)	PCC-10: Plain cement concrete work in foundation with minimum compressive strength of 10 MPa at 28 days (sugessted mix proportion 1:3:6) on standard cylinder as per standard practice of Code AASHTO/ ASTM and cement conforming to BDS EN 197-1 : 2003 CEM-II/A-L/M/V/W 42.5N, sand of minimum FM 1.8 and 20mm down well graded 1st class/ picked brick chips (LAA value not exceeding 40) conforming to ASTM C 33 including breaking bricks into chips, shuttering, mixing by concrete mixer machine, casting, laying compacting and curing for the requisite period etc. all complete as per direction of the E-I-C. Additional quantity of cement to be added if required to attain the strength at the contractor's own cost.	Cum	45.390				
27	1	04.09.03 (LGED)	RCC-25SCCM: Reinforced cement concrete work with minimum cement content relates to mix ratio 1:1.5:3 and maximum water cement ratio 0.4 having minimum required average strength, $f'_{cr} = 33.5$ MPa and satisfying a compressive strength $f'_c = 25$ MPa at 28 days on standard cylinders as per standard practice of Code AASHTO/ ASTM and cement conforming to BDS EN 197-1 : 2003 CEM II/A-L/M/V/W 42.5N, high range water reducing admixture of complying type A or F under ASTM C 494 (Doses of admixture to be fixed by the mix design), sand of minimum FM 2.5 and 20mm down well graded crushed stone chips broken from boulders (Preferably stone chips from Madhyapara, Dinajpur, LAA value not exceeding 30) conforming to ASTM C33 including breaking chips, screening through proper sieves, cleaning, placing shutter in position, making shutter water-tight properly, placing reinforcement in position, mixing in standard mixture machine with hopper, maintaining allowable slump of 75mm to 100mm, casting in forms, compacting by mechanical vibrator machine, curing for 28 days, removing centering-shuttering after approved specified time period, other incidental charges, etc. all	cum	461.260				

			complete as per drawing, specification & direction of the E-I-C. The cost of reinforcement and it's fabrication, welding, coupling, placing, binding etc. is not included but the cost of admixture is included in this unit rate. Additional quantity of cement to be added if required to attain the strength at the contractor's own cost. [Using Concrete Mixture Machine and retail rate of Cement] 04.09.03.01: For pile caps, abutment base, facing elements of Reinforced/ Mechanically Stabilized Earth Structure, bottom slab of Box Culvert etc.						
28	1	04.09.03 (LGED)	RCC-25SCCM: Reinforced cement concrete work with minimum cement content relates to mix ratio 1:1.5:3 and maximum water cement ratio 0.4 having minimum required average strength, $f'_{cr} = 33.5$ MPa and satisfying a compressive strength $f'_c = 25$ MPa at 28 days on standard cylinders as per standard practice of Code AASHTO/ ASTM and cement conforming to BDS EN 197-1 : 2003 CEM II/A-L/M/V/W 42.5N, high range water reducing admixture of complying type A or F under ASTM C 494 (Doses of admixture to be fixed by the mix design), sand of minimum FM 2.5 and 20mm down well graded crushed stone chips broken from boulders (Preferably stone chips from Madhyapara, Dinajpur, LAA value not exceeding 30) conforming to ASTM C33 including breaking chips, screening through proper sieves, cleaning, placing shutter in position, making shutter water-tight properly, placing reinforcement in position, mixing in standard mixture machine with hopper, maintaining allowable slump of 75mm to 100mm, casting in forms, compacting by mechanical vibrator machine, curing for 28 days, removing centering-shuttering after approved specified time period, other incidental charges, etc. all complete as per drawing, specification & direction of the E-I-C. The cost of reinforcement and it's fabrication, welding, coupling, placing, binding etc. is not included but the cost of admixture is included in this unit rate. Additional quantity of cement to be added if required to attain the strength at the contractor's own cost. [Using Concrete Mixture Machine and retail rate of Cement]	cum	416.060				

			04.09.03.02.01: For diaphragm walls, wing walls, piers, columns, projected pile cap above water level, pier caps, abutments of bridges and vertical members of box culverts For height up to 5m						
29	1	04.09.03 (LGED)	RCC-25SCCM: Reinforced cement concrete work with minimum cement content relates to mix ratio 1:1.5:3 and maximum water cement ratio 0.4 having minimum required average strength, $f'_{cr} = 33.5$ MPa and satisfying a compressive strength $f'_c = 25$ MPa at 28 days on standard cylinders as per standard practice of Code AASHTO/ ASTM and cement conforming to BDS EN 197-1 : 2003 CEM II/A-L/M/V/W 42.5N, high range water reducing admixture of complying type A or F under ASTM C 494 (Doses of admixture to be fixed by the mix design), sand of minimum FM 2.5 and 20mm down well graded crushed stone chips broken from boulders (Preferably stone chips from Madhyapara, Dinajpur, LAA value not exceeding 30) conforming to ASTM C33 including breaking chips, screening through proper sieves, cleaning, placing shutter in position, making shutter water-tight properly, placing reinforcement in position, mixing in standard mixture machine with hopper, maintaining allowable slump of 75mm to 100mm, casting in forms, compacting by mechanical vibrator machine, curing for 28 days, removing centering-shuttering after approved specified time period, other incidental charges, etc. all complete as per drawing, specification & direction of the E-I-C. The cost of reinforcement and it's fabrication, welding, coupling, placing, binding etc. is not included but the cost of admixture is included in this unit rate. Additional quantity of cement to be added if required to attain the strength at the contractor's own cost. [Using Concrete Mixture Machine and retail rate of Cement] 04.09.03.02.02: For diaphragm walls, wing walls, piers, columns, projected pile cap above water level, pier caps, abutments of bridges and vertical members of box culverts For height above 5m to 10m	cum	82.790				
30	1	04.09.03 (LGED)	RCC-25SCCM: Reinforced cement concrete work with minimum cement content relates to mix ratio 1:1.5:3 and	cum	38.870				

			recorded only on standard mass per unit length of bars, while dia of bars exceeds its standard) 08.1.2: Grade 400 (B400DWR / B420DWR: complying BDS ISO 6935-2:2016 / ASTM A615) ribbed or deformed bar produced and marked according to Bangladesh standard, with minimum yield strength, fy (ReH)= 400 MPa but fy not exceeding 480 MPa and whatever is the actual yield strength within allowable limit as per BNBC/ ACI 318, the ratio of ultimate tensile strength fu to yield strength fy, shall be at least 1.25 and minimum elongation after fracture and minimum total elongation at maximum force is 17% and 8% respectively : up to ground floor.						
32	1	26.42 (PWD)	Supplying, fitting and fixing of G.I. pipe with all special fittings, such as bends, elbows, sockets, reducing sockets, Tee, unions, jam-nuts etc. including cutting trenches where necessary and fitting the same with earth duly rammed and fixing in walls with holder bats and making hole in floors, walls and consequent mending good the damages etc. all complete in all respects approved and accepted by the Engineer- in- charge. 26.42.5: 40 mm dia G.I. pipe with wall thickness 3.25 mm, outside diameter min 46.5 mm, weight 3.83 kg/m, can withstand min 50 kg/cm2 hydraulic pressure.	m	87.240				
33	1	76-630-00 (BWDB)	Supply and fitting and fixing 23cm wide P.V.C water stops having minimum strength of 13.80N/mm2 at 225% elongation and of approved quality in antraction and expansion joints with necessary arrangements for modification in shuttering and keeping the water stop in position etc. complete as per design, specification and direction of Engineer in charge. 76-630-10: 3 bulb type.	m	45.000				
34	1	76-170-00 (BWDB)	M.S. Work in plates, angles, channels, flat bars, Tees etc. including fabricating, machining, cutting, bending, welding, forging, drilling, revetting, embedding anchor bars, staging and fitting, fixing, local handling etc. complete with energy consumption and supply of labours including the cost of materials as per design, specification and direction of Engineer in charge.	Kg	26695.940				
35	1	72-130-00 (BWDB)	Synthentic enamel painting to steel surfaces/ gates/ hoists etc. with paint of approved colour (2 coats over a coat of	Sqm	50.100				

			priming) including preparation of the surface with steel brush, emery paper and cleaning etc. complete including the cost of all materials as per direction of Engineer in charge. 72-130-10: 2 coats over a priming coat.						
36	1	04-280-00 (BWDB)	Constructing at site, cement mortar gauge on masonry wall, including engraving in meter, decimeter & centimeter, painting and figuring with black and red water proof paint, etc. complete as per direction of Engineer in charge. 04-280-10: 150mm x 25mm	m	11.200				
37	1	16-560-00 (BWDB)	Back filling in hydraulic structures including all leads and lifts with sand in 150mm layer including watering, ramming, compacting to 30% relative density etc. complete by compactor or any other suitable method as per direction of Engineer in charge. 16-560-20: Sand of FM ≥ 0.80	Cum	4968.210				
38	1	16-550-00 (BWDB)	Back filling in hydraulic structures and slope building in protective works including all leads and lifts with selected local soil in layer of 150mm including watering, ramming etc. complete compacted to 20% relative density by compactor or any other suitable method as per direction of Engineer in charge.	Cum	9096.470				
39	1	40-520-00 (BWDB)	Supplying and laying dry 1st class or pick jhama chips as filter in two layers (top and bottom) as per specific size, range and gradation, including breaking chips, grading, preparation of surface, compacting each layer etc. complete with supply of all materials and as per direction of Engineer in charge: 40-520-20: Well graded between 40mm to 20mm size.	Cum	105.300				
40	1	40-520-00 (BWDB)	Supplying and laying dry 1st class or pick jhama chips as filter in two layers (top and bottom) as per specific size, range and gradation, including breaking chips, grading, preparation of surface, compacting each layer etc. complete with supply of all materials and as per direction of Engineer in charge: 40-520-30: Well graded between 20mm to 5mm size. (Combination of sub-item 10 & 30 or 20 & 30 shall be used)	Cum	105.300				
41	1	40-550-00 (BWDB)	Supplying and laying sand as filter layers as per specific size ranges and gradation including preparation of surface, compacting in layer etc. complete with supply of all materials and as per direction of Engineer in charge. 40-550-	Cum	108.270				

			20: FM : 1.5 to 2.0						
42	1	40-500-00 (BWDB)	Supplying and placing non-woven needle punched type geotextile fabric (97% Polypropylene Fabric and additives shall be 3%, Carbon Black 2% and Antioxidants 1%, may be mixed as additives, unit weight : 855 Kg/m ³ to 946 Kg/m ³) as filter materials of elongation at maximum force machine direction (MD) >=60% and < = 100 % , elongation at maximum force (CMD) = > 40% and < = 100% ,horizontal and vertical permeability (under 2 kn/m ² pressure)= >2x10E-3 m/sec. for effective erosion protection in hydraulic structures/river training works including local handling, placing in position, providing machine seamed joints (with 100% polypropylene or nylon thread) or 35cm lap in dry condition or minimum 100cm lap under water including protecting the geotextile material from UV ray and from any other damages including supply of all materials, labours, equipment's etc. complete as per direction of Engineer in charge. (Geotextile delivered at site should be certified by ISO and clearlylabelled with brand name and grade printed at regular intervals across the body of the fabric). 40-500-40: Mass = >400 gm/m ² , thickness(Under 2 kpa pressure) = >3.00 mm, EoS< =0.08mm, strip tensile strength = >23 kn/m, grab strength = >1500 N, CBR puncture resistance = >3800 N	Sqm	1169.950				
43	1	40-230-00 (BWDB)	Manufacturing and supplying C.C. blocks in leanest mix. 1:2:4 with cement, sand (FM >=2.0) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 18 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering and stacking in measurable stacks etc. complete including supply of all materials (steel shutter to be used) as per direction of Engineer in charge. 40-230-90: Block Size: 50cmx50cmx20cm.	Each	1118				
44	1	40-230-00 (BWDB)	Manufacturing and supplying C.C. blocks in leanest mix. 1:2:4 with cement, sand (FM >=2.0) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 18 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering and stacking in measurable stacks	Each	1099				

			etc. complete including supply of all materials (steel shutter to be used) as per direction of Engineer in charge. 40-230-45: Block Size: 35cmx35cmx35cm.						
45	1	40-230-00 (BWDB)	Manufacturing and supplying C.C. blocks in leanest mix. 1:2:4 with cement, sand (FM >=2.0) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 18 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering and stacking in measurable stacks etc. complete including supply of all materials (steel shutter to be used) as per direction of Engineer in charge. 40-230-30: Block Size: 45cmx45cmx30cm	Each	4301				
46	1	40-270-00 (BWDB)	Labour charge for protective works in laying CC blocks of different sizes including preparation of base, watering and ramming of base etc. complete as per direction of Engineer in charge. 40-270-20: 200 m to 500 m.	Cum	364.310				
47	1	76-242-00 (BWDB)	Manufacturing & Supplying of M.S. Vertical Lift Gate shutter having 10mm thick M.S. skin plate and stiffener with minimum 75mm x 75mm x 9mm M.S. angle (Top & Bottom beam, Horizontal main beam and End vertical beam) as frame, 28mm x 53mm x 15mm P-type top & side rubber seal fixed with 10mm x 55mm S.S. counter shank bolts with nuts and 25mm x 6mm S.S. strip as clamp drilled spaces @ 150mm c/c, Utype or Flat bottom rubber seal, threaded stem attachment with bottom socket, nut-bolts, cotter pin and washer as per approved design including the cost of all materials of proper grade & brand new with a prime coat of redoxide and three final coat of coaltar epoxy paint (marine quality) where necessary as per specification and direction of Engineer in charge. 76-242-50: Size 1.65m x 1.875m (Vent 1.5m x 1.8m)	Each	3				
48	1	76-252-00 (BWDB)	Manufacturing & Supplying of M.S. Flap Gate shutter of 10mm thick M.S. skin plate and stiffener with minimum 75mm x 75mm x 9mm M.S. angle as frame, horizontal & vertical beam, 28mm x 53mm x 15mm P-type rubber seal, fixed with 10mm x 55mm S.S. counter shank bolts with nuts and 25mm x 6mm S.S. strip as clamp drilled spaces @ 150mm c/c, hinge assy with gate and wall bracket, link arm of (16-20)mm thick M.S. plate, 4 nos	Each	3				

			?(35-50)mm S.S. hinge pin with proper thread, nut-bolts, cotter pin and washer as per approved design including the cost of all materials of proper grade & brand new with a prime coat of red-oxide and three final coat of coaltar epoxy paint (marine quality) where necessary as per specification and direction of Engineer in charge. 76-252-50: Size 1.65m x 1.95m (Vent 1.5m x 1.8m)						
49	1	76-260-00 (BWDB)	Labour charge for fitting and fixing of M.S. vertical lift gate/ flap gate shutters of different size including making holes in concrete for hooking arrangements with supply of necessary materials, tools and other accessories required for fitting the same to regulator/slucie and mending the damages with CC (1:2:4), removing the spoils etc. complete including the cost of all materials as per direction of Engineer in charge. 76-260-20: Size 1.95m x 1.35m or 1.95m x 1.65m.	Each	6				
50	1	76-190-00 (BWDB)	Manufacturing, supplying and Installation of Padestal type lifting device for slide gate with 63mm dia threaded steel shaft, 146mm outer dia bronze nut, thrust bearing, steel bevel gear etc. as per approved design including supply of all components, labours with a prime coat of redoxide where necessary etc. complete including the cost of all materials as per specification and direction of Engineer in charge.	Each	3				
51	1	76-780-00 (BWDB)	Supplying and fitting, fixing dowel bar in expansion each joints of hydraulic structures with 32mm dia M.S. plain bar 2000mm long, hooked in one end and painted at the other end for a length of 900mm with 40mm dia 100mm long G.I./M.S. pipe closed at one end and filled with 30mm thick compressible filter, including placing in position, binding with G.I. Wire etc. complete as per direction of Engineer in charge.	Each	74.000				
52	1	16-470-00 (BWDB)	Earth work by manual labour, in all kinds of soil in removing the cross bundh/ ring bundh, including all leads and lifts complete and placing the spoils to a safe distance, (minimum 15m apart from the bank) as per direction of Engineer in charge.	Cum	6503.640				
53	1	16-240-00 (BWDB)	Earth work by Mechanical Excavator (Long Boom) in constructing/ resectioning of embankment/canal bank/ road etc. compacted to 85%/90% maximum dry density at	Cum	4234.330				

			optimum moisture content, with reference to laboratory density test AAHSTO modified hammer, with clayey soil(minm 30% clay, 0 40% silt, 0-30% sand) within the initial lead of 30m and all lifts including throwing the spoils to profiles in layers not exceeding 230mm in thickness with clod breaking to a maximum size of 100mm, benching the side slopes, removing roots and stumps of trees of girth upto 200mm from the ground, stripping/ploughing the base of embankment and borrow pit area, dug bailing, rough dressing including 150mm cambering at the centre of crest etc. complete, including maintenance of the same for 6 months after completion, (compaction will be done by the contractor with approved equipment, including all ancillary charges for compaction and testing) as per direction of Engineer in charge. 16-240-10: Embankment by Mech. Equipment; ht: 0 to 4m; 85% comp						
54	1	48-100-00 (BWDB)	Fine dressing and close turfing of the slopes and the crest of embankment with 75mm thick, good quality durba or charkanta sods of size 200mm x 200mm, with all leads and lifts, including ramming, watering until the turf grows properly, maintaining etc. complete (measurement will be given on well grown grass only). as per direction of Engineer in charge.	Sqm	21440.000				
55	1	16-410-00 (BWDB)	Earth work by Mechanical Excavator (Long Boom) in all kinds of soil in excavation / re-excitation of channel/canal/khal etc. Including disposal of spoil-soil upto 30m away from the point of excavation with rough dressing and levelling etc. complete as per direction of Engineer-in charge.	Cum	22611.770				
56	1	16-400-00 (BWDB)	Earth work by manual labour in all kinds of soil in excavation or reexcavation of channels with the initial lead of 30m and lift of 1.5m including levelling, dressing and throwing the spoils to profile with breaking clods, rough dressing, clearing jungles including cutting trees upto 200mm girth, dug bailing etc. complete as per direction of Engineer in charge.	Cum	14115.160				
57	1	16-420-00 (BWDB)	Extra Rate for every additional shift of Dredged/Excavated earth or shifting of earth by Mechanical Excavator (Long Boom) of 30m or part thereof beyond the initial shift of 30m upto a maximum of 9 shift for all kind of earthwork shift.	Cum	4234.550				

			(Unit: per shift per cum)						
58	1	16-720-00 (BWDB)	Filling ditch/pond/channel/khal etc or land development/ improvment by dredged earth from river bed (all kind of soil but excluding organic material) , carried Bulkhead/cargo/boat or any other mean, loading and unloading/Disposing/placing the dredged materials in the designated area upto 1 km from river bank by bulkhead dredger including , maintaining slopes, levelling and dressing in layers upto finished level with all lifts & leads etc. all complete as per direction of the Engineer in charge. 16-720-10: Bulkhead/cargo/boat or any other means within 1 km along the river	Cum/ Km	5522.800				
59	1	16-720-00 (BWDB)	Filling ditch/pond/channel/khal etc or land development/ improvment by dredged earth from river bed (all kind of soil but excluding organic material) , carried by Bulkhead/cargo/boat or any other mean, loading and unloading/Disposing/placing the dredged materials in the designated area upto 1 km from river bank by bulkhead dredger including, maintaining slopes, levelling and dressing in layers upto finished level with all lifts & leads etc. all complete as per direction of the Engineer in charge. 16-720-20: Bulkhead/cargo/boat or any other means: 2nd km and above.	Cum/ Km	5522.800				
60	1	16-100-00 (BWDB)	Erection of bamboo profile with full bamboo posts and pegs not less than 60mm in diameter and coir strings etc. complete as per direction of Engineer in charge.	nos	22				
61	1	10-200-00 (BWDB)	Topography Survey of embankment/road/canal/river Section (Section with upto 50m), including cost of all necessary equipment (Level machine, Hand GPS, DGPS etc.), Necessary Personnel (River Morphology Expert for data consistency checking, Engineer/Survey specialist for data processing with survey software and prepare necessary table, Graph and Morphological Parameter Calculations, Surveyor & Unskilled labour for field data collection), Accommodation, Transportation from Headquarter to site and site movement and shaded boat for bathymetric survey for field survey Team including necessary fuels and lubricant. Other necessary auxillary items such as survey flags, pegs with provision for submission of report in hard binded copies (at	nos	28				

			least 6 copies required), soft copies and raw survey data with provision of 10% random re-survey for data consistency checking as per direction of Engineer Charge. 10-200-30: Section interval: 101m to 150 m						
62	1	10-250-00 (BWDB)	Level Flying for survey work Including cost of all necessary equipments (Level Machine, Hand GPS, DGPS etc.), Necessary Personnel (River Morphology Expert for data consistency checking, Engineer/Survey Specialist for data consistency checking, Engineer/Survey Specialist for data processing with survey software and prepare necessary Table, Graph and Morphological Parameter Calculations, Surveyor & Unskilled Labour for field data collection), Accommodation, Transportation from Headquarter to site and site movement and shaded boat for bathymetric survey for field Survey Team including necessary fules and Lubricant, other necessary auxiliary items with provision for submission of report in hard binded copies(at least 6 copies required), soft copies and raw survey data Consistency checking as per direction of Engineer in Charge.	nos	4.200				
63	1	32.6.1.1 (PWD)	Dismantling of R.C.C. beam, lintel, column, drop wall, sun shade from any height and removal of debris to a safe distance.	Cum	126.000				
64	1	01.1.6 (PWD)	Providing and maintenance one project profile signboards to be placed at a suitable place of the site including submission of proposals for the materials of the signboards and text layout containing 3D picture, safety instructions, project information with security light etc. to the Engineer-in-charge for approval which will be positioned as directed by the Engineer-in-charge and removing the same on completion of the works or as instructed by the Engineer-in-charge.	Sqm	3.750				
65	1	01.7 (PWD)	Mobilization and cleaning site before commencing actual physical work and during contract period and demobilization after completion of the works under contract to be accepted by the Engineer-in-charge. This work shall also cover cleaning and clearing, cutting or filling, dressing the project area on and in the ground to an extent that all the events of works of the project can be executed smoothly in a working environment with a	Sqm	3000.000				

			particular attention on safety and security in all respects, and to stockpile the end outcome to a place for disposal agreed by the Engineer-in-charge, where, payments are to be based on ground area determined by the Engineer-in-charge and be proportionate to the percentage progress of work under contract as a whole in all respects and approved by the Engineer-in-charge.						
66	1	12-110-00 (BWDB)	Mobilization of complete well point system, equipments and accessories from one place to another including loading and unloading as per direction of Engineer in charge. 12-110-10: Within 1.00 km.	ps/ km	1				
67	1	12-120-00 (BWDB)	Installation of well point dewatering set including supply of all accessories, materials and labours for one 5 cusec vacuum pump for minimum 100 well points in controlling subsurface water during construction, providing shrouding materials, conducting test operation and subsequent removal of the complete dewatering set in accordance with standard specification and field requirement, as per direction of Engineer in charge.	set	1				
68	1	12-150-00 (BWDB)	Operation of well point system, by 5 cusec vacuum pump for dewatering of subsurface water, maintaining draw down records including supply of necessary fuels, lubricants, operation personnel and maintenance of the same upto completion of the work in accordance with standard specification and direction of Engineer in charge.	hours	1200.000				
69	1	12-180-00 (BWDB)	Installation of dewatering tubewells at site for controlling subsurface water during construction, including supply of all materials, equipments, fuels, lubricants etc. providing shrouding materials, conducting well testing & development and subsequent removal of complete dewatering system in accordance with standard specification and field requirement etc. complete including sealing of hole, mobilization and demobilization of equipments and accessories (contractor has to prepare and submit a dewatering plan based on field requirement to the competent authority for approval, prior to installation of the tube well) as per direction of Engineer in charge. 12-180-10: 18.0m depth including strainer (as per design) and 75mm dia tubewell (bore hole 200mm dia) with PVC pipe and strainer.	No.	1				

70	1	12-200-00 (BWDB)	Operation of tubewell by centrifugal pump for dewatering of subsurface water, maintaining drawdown records including supply of necessary fuels, lubricants, operation personnel and maintenance of the same upto the completion of the work as per specification and direction of Engineer in charge. 12-200-20: 0.50 cusec capacity	hours	400.000				
71	1	12-160-00 (BWDB)	Demobilization of complete well point system, equipments and accessories from one place to another including loading and unloading as per direction of Engineer in charge. 12-160-10: Within 1.00 km.	ps/ km	1				
							Grand Total :		

Schedule of Day works

Table Name :									
Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Nominal Quantity	Unit Price in Figures (BDT)	Unit Price in Words (BDT)	Total Price in Figures (BDT)	Total Price in Words (BDT)
N/A	1	N/A	Construction of Regulator (3-Vent: 1.50m x 1.80m)	N/A	1				
							Grand Total :		

Discount Form

Table Name : Unconditional Discount Form	
Discount in Percentage (%) [In figure]	Discount in Percentage (%) [In word]

Provisional Sum

Instruction for Procuring Entity (PE):

This is an optional form.

PE may fill it if require. If it is filled then PE has to add this form to Grand Summary.

Table Name : Provisional Sum								
Item No	Description of Specified Provisional	Measurement Unit	Quantity	Unit Price In figures	Unit Price In	Total Price In figures	Total Price In	Tenderer Response

NO	Provisional Sums	Unit		figures (BDT)	words (BDT)	figures (BDT)	words(BDT)	Response
----	---------------------	------	--	------------------	----------------	------------------	------------	----------